Name: Castillo, Joshua L.	Date Performed: 3/21/24			
Course/Section: CPE31S1	Date Submitted: 3/24/2024			
Instructor: Dr. Jonathan Tylar	Semester and SY:			
Activity 7: Managing Files and Creating Poles in Angible				

Activity 7: Managing Files and Creating Roles in Ansible

1. Objectives:

- 1.1 Manage files in remote servers
- 1.2 Implement roles in ansible

2. Discussion:

In this activity, we look at the concept of copying a file to a server. We are going to create a file into our git repository and use Ansible to grab that file and put it into a particular place so that we could do things like customize a default website, or maybe install a default configuration file. We will also implement roles to consolidate plays.

Task 1: Create a file and copy it to remote servers

- 1. Using the previous directory we created, create a directory, and named it "files." Create a file inside that directory and name it "default_site.html." Edit the file and put basic HTML syntax. Any content will do, as long as it will display text later. Save the file and exit.
- 2. Edit the *site.yml* file and just below the *web_servers* play, create a new file to copy the default html file for site:
 - name: copy default html file for site

tags: apache, apache2, httpd

copy:


src: default_site.html


dest: /var/www/html/index.html

owner: root group: root mode: 0644

3. Run the playbook *site.yml*. Describe the changes.

4. Go to the remote servers (web_servers) listed in your inventory. Use cat command to check if the index.html is the same as the local repository file (default_site.html). Do both for Ubuntu and CentOS servers. On the CentOS server, go to the browser and type its IP address. Describe the output.






remote_src: yes mode: 0755 owner: root group: root

- 2. Edit the inventory file and add workstations group. Add any Ubuntu remote server. Make sure to remember the IP address.
- 3. Run the playbook. Describe the output.

4. On the Ubuntu remote workstation, type terraform to verify installation of terraform. Describe the output.

```
joshua@ControlNode1:~$ terraform
Usage: terraform [-version] [-help] <command> [args]
The available commands for execution are listed below.
The most common, useful commands are shown first, followed by
less common or more advanced commands. If you're just getting
started with Terraform, stick with the common commands. For the
other commands, please read the help and docs before usage.
Common commands:
    applv
                       Builds or changes infrastructure
    console
                       Interactive console for Terraform interpolations
    destroy
                       Destroy Terraform-managed infrastructure
                       Workspace management
    env
                       Rewrites config files to canonical format
    fmt
                       Download and install modules for the configuration
    aet
    graph
                       Create a visual graph of Terraform resources
    import
                       Import existing infrastructure into Terraform
    init
                       Initialize a Terraform working directory
                       Obtain and save credentials for a remote host
    login
                       Remove locally-stored credentials for a remote host
    logout
                       Read an output from a state file
    output
    plan
                       Generate and show an execution plan
    providers
                       Prints a tree of the providers used in the configuration
```



Task 3: Create roles

1. Edit the site.yml. Configure roles as follows: (make sure to create a copy of the old site.yml file because you will be copying the specific plays for all groups)

```
hosts: all
become: true
pre_tasks:

    name: update repository index (CentOS)

  tags: always
  dnf:
    update_cache: yes
  changed when: false
  when: ansible distribution == "CentOS"
- name: install updates (Ubuntu)
  tags: always
  apt:
    update cache: yes
  changed when: false
  when: ansible_distribution == "Ubuntu"
hosts: all
become: true
roles:
  - base
hosts: workstations
become: true
roles:

    workstations

hosts: web servers
become: true
roles:

    web_servers

hosts: db servers
become: true
roles:
  - db servers
hosts: file_servers
become: true
roles:
  - file servers
```

Save the file and exit.

2. Under the same directory, create a new directory and name it roles. Enter the roles directory and create new directories: base, web_servers, file_servers, db_servers and workstations. For each directory, create a directory and name it tasks.

```
joshua@ManagedNode:~/CPE232_CASTILL01$ cd roles
joshua@ManagedNode:~/CPE232_CASTILL01/roles$ tree

base
    tasks
    main.yml

db_servers
    tasks
    main.yml

file_servers
    tasks
    main.yml

web_servers
    tasks
    main.yml

workstations
    tasks
    main.yml

dorectories, 5 files
joshua@ManagedNode:~/CPE232_CASTILL01/roles$
```

3. Go to tasks for all directory and create a file. Name it main.yml. In each of the tasks for all directories, copy and paste the code from the old site.yml file. Show all contents of main.yml files for all tasks.

Main.yml

base main.yml

workstations Main.yml

web_servers Main.yml

```
main.yml
~/CPE232_CASTILLO1/roles/web_servers/tasks
main.yml
- name: install apache and php for Ubuntu servers
   tags: apache, apache2, ubuntu
   apt:
     name:
       - libapache2-mod-php
     state: latest
   when: ansible_distribution == "Ubuntu"
  - name: install apache and php for CentOS servers
   tags: apache,centos,httpd
   dnf:
     name:
     state: latest
   when: ansible_distribution == "CentOS"
 - name: start httpd (CentOS)
   tags: apache, centos, httpd
   service:
     name: httpd
     state: started
     enabled: true
   when: ansible_distribution == "CentOS"
```

file_servers Main.yml

```
Open > In site.yml

site.yml

name: install samba package
tags: samba
package:
name: samba
state: latest
```

db_servers Main.yml

```
main.yml
site.yml
                                         main.yml
                                                                       main.yml
- name: install mariadb package (CentOS)
    tags: centos,db,mariadb
   yum:
     name: mariadb-server
     state: latest
   when: ansible_distribution == "CentOS"
- name: "mariadb- Restarting/Enabling"
  service:
   name: mariadb
   state: restarted
   enabled: true
- name: install mariadb package (Ubuntu)
 tags: db,mariadb,ubuntu
  apt:
   name: mariadb-server
   state: latest
   when: ansible_distribution == "Ubuntu"
```

4. Run the site.yml playbook and describe the output.

file_servers main.yml output

In this output we break down the tasks into their respective components.

After the tasks, I added the changes in my github repository.

note: i only used 3 vm's at a time because of the slow responsiveness of the device, i switch back to 1 vm(db_servers) once i'm done configuring its components.

Reflections:

Answer the following:

- 1. What is the importance of creating roles?

 Creating roles in Ansible organizes playbook management by distributing the tasks into their respective roles making it a reusable component, it also allows its user to reuse a playbook for other tasks which saves time.
- 2. What is the importance of managing files?

file management is important for accurate configurations and security against unauthorized access, lastly it optimizes system efficiency.